



अधीक्षण अभियंता का कार्यालय
OFFICE OF THE SUPERINTENDING ENGINEER
कार्य स्थापना अनुभाग, WORKS ESTABLISHMENT SECTION
राष्ट्रीय प्रौद्योगिकी संस्थान कर्नाटक, सुरतकल
NATIONAL INSTITUTE OF TECHNOLOGY KARNATAKA, SURATHKAL

पोस्ट श्रीनिवासनगर, मंगलूरु - 575025, कर्नाटक, भारत. / Post Srinivasnagar, Mangaluru - 575025, Karnataka, INDIA.
Phone: [0824] - 2473029, 2473028 Email: sa@nitk.edu.in Website: <http://www.nitk.ac.in>

No.SE/Civil/2026-27/E-II(35-A) /

Date: 30-07-2026

BRIEF TENDER NOTIFICATION

Sealed tenders on percentage basis are hereby invited from the registered civil contractors of KPWD / CPWD etc., on behalf of the Director, National Institute of Technology Karnataka Surathkal for the work noted below. The tenders shall be received in this office on **06-08-2026 up to 10:00AM**. The tenders will be opened on the same day by the undersigned if possible.

Sl. No.	Name of the works	Estimate amount put to tender (Rs.) (Including GST)	E.M.D
1.	Removal of Vegetation growth over chajjas and raising of vent pipe height at the IT department in NITK	2,98,169.00	In the form of bid Security Declaration

Eligibility Class of Contractor:

Civil: Karnataka PWD class IV or above / Central PWD class V or above

Terms and Conditions:

1. The tendering bidder must submit a 'Bid Security Declaration' in the case of NSIC/MSME/ Startups bidders seeking exemption from EMD/Bid Security, they should be attaching then SIC/MSME/ Startups certificate (obtained for relevant NIC & Activity), otherwise Bid Security Declaration must be submitted.
2. The tender receiving after due date will be rejected.
3. Envelope super scripted as name of the work and due date and addressed to as 'The Superintending Engineer, NITK Surathkal, Post Srinivasnagar, Mangaluru - 575 025' be sent so as to reach this office on or before the due date mentioned.
4. The tentative Bill of Quantities (BOQ) for the work is enclosed. The intending contractor shall quote a **single percentage** rate, either above, below or at par with the total amount of the approved estimate, on the firm's letterhead.
5. The contractor must submit the copy of valid registered certificates of PWD license, EPF, ESI, and GST & PAN
6. The Contractor must visit the site and analyze the nature of work before submitting the tender quotation.
7. The work shall be completed within 21 days from the date of issue of the work order. In case of delay, a penalty at the rate of 1% of the work order value per week, shall be levied.
8. If the successful bidder (L1) fails to commence the work or refuses to execute the work after issue of the work order without valid justification acceptable to the Institute, the Institute reserves the right to cancel the work order and blacklist/debar the contractor from participating in any quotation/tender process of the Institute for a period of up to three (3) years.
9. The contractor shall commence the work from the date of issue of the Work Order.
10. The contractor shall submit a detailed work schedule/programme to the SE Office within 7 days from the date of issue of the Work Order for review and record.
11. The contractor shall maintain a stage-wise approval register for obtaining the signatures of the competent authority at various stages of the work, as directed by the Engineer-in-Charge, prior to execution of the respective activities. Failure to obtain the required approvals or to maintain the register shall be treated as a

serious violation of the contract conditions and may result in cancellation of the work at the contractor & risk and cost, without entitlement to any claim arising therefrom.

12. The Contractor shall provide a valid official e-mail ID for all official communications.
13. Security Deposit at the rate of 5% of the work value shall be deducted from the contractor's bill. The amount may be claimed after six months from the date of satisfactory completion of the work.
14. The undersigned reserve the right of rejecting all the tenders without assigning any reasons thereof.

R. Nayak 30/12/16
Superintending Engineer
NITK Surathkal

अधीक्षक अभियंता / Superintending Engineer
कार्य स्थापना विभाग / Works Establishment Section
राष्ट्रीय प्रौद्योगिकी संस्थान कर्नाटक, सुरथकल
National Institute of Technology Karnataka, Surathkal
पोस्ट श्रीनिवासनगर, - ५७५ ०२५ / Post Srinivasnagar - 575 025



Si No:	Details of work	Quantity	UOM
1	Removing vegetation, weeds, creepers, bushes and other unwanted growth from chajjas, projections and external faces of buildings at all heights, including uprooting and removal of roots, application of approved herbicide/weedicide to prevent regrowth, removal of roots penetrated into rainwater pipes and other service lines, collection, lowering and disposal of all removed vegetation and debris at the designated dumping yard, complete as per the direction of the Engineer-in-Charge.	85.05	Rmt
2	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40 mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube chalis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. Note:- (1) The elevational area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works.	394.07	Sqm
3	Providing core cutting in RCC Chejja of required diameter up to 150 mm, including finishing the edges with cement mortar, and making good the disturbed surfaces, complete with cost of materials, labour and cleaning of debris, as per specifications and directions of the Engineer-in-charge.	28.00	Number
4	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.		
i	75 mm diameter	75.6	Rmt
ii	110 mm diameter	100.8	Rmt
5	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Vent Cap		
i	75 mm	6.3	Number
ii	110 mm	8.4	Number

R. N. Nigam

अधीक्षक अभियंता
आवक व निष्कासक विभाग
कार्य स्थायी अड्डा
National Institute
पोस्ट श्रीनिवासपुर, - 386 001

Engineer
Joint Section
सुरथकल Surathkal
Surathkal, Surathkal
Surathkal - 386 025

